

SUPPLEMENTAL/BID BULLETIN

Republic of the Philippines
UNIVERSITY OF THE PHILIPPINES BAGUIO
Governor Pack Road, Baguio City
(074) 446-9973/442-3888/442-3484
Website: www.upb.edu.ph; E-mail: www.bac.upbaguio@up.edu.ph

ADDENDUM NO. 2018-013

CONSTRUCTION OF CAMPUS-WIDE INTERCONNECTIVITY AND ACCESSIBILITY 23 November 2018

This Addendum No. 2018-013 is issued to supplement/amend details in the Bill of Quantities and plans for the Project: CONSTRUCTION OF CAMPUS-WIDE INTER-CONNECTIVITY AND ACCESSIBILITY. This shall form an integral part of the Bid Documents. Prospective Bidders shall take note of the following information and incorporate it in their bids.

The following information issued with the original bid set are to be replaced in their entirety by the list issued by this addendum:

DELETED ITEMS FROM THE BID FORM

DIVISION 02 - EXISTING CONDITIONS

KOLEHIYO NG AGHAM BUILDING(KA)- CANTEEN Connection

1. Demolition of walls, windows, and balcony railing
2. Demolition of windows
3. Demolition of canteen backhouse
4. Demolition of existing door and windows
5. Demolition of existing outdoor steel staircase

ISABELO DELOS REYES BUILDING(IDR) - CANTEEN Connection

1. Demolition of existing stairs
2. Demolition of existing column, roof and trusses
3. Demolition of existing walls and windows
4. Demolition of existing ramp and handrail

DIVISION 03 - CONCRETE

ISABELO DELOS REYES BUILDING(IDR) - STAIR @ EAST

1. 34.8mPA (5000PSI @ 28 days) Elevator Foundation Slab serving as pile cap and 4 sets of piles: Foundation Slab is 3000mm x 3000mm x 900mm reinforced top and bottom with 20mmØ G60 RSB spaced at 150mm bothways; Piles are 500mmØ x 6000mm reinforced with 8-20mmØ G60 with 10mmØ G60 circular ties; tie wires included; provide 50 mm thk gravel base; Labor for Bore Piling included
2. 34.8mPA (5000PSI @ 28 days), Grade Beam is 300mm x 600mm; Piles are 600mmØ x 6000mm reinforced with 8-20mmØ G60 with 10mmØ G60 circular ties; tie wires included; provide 50 mm thk gravel base
3. 200mm 34.48MPa Cast in place reinforced Concrete Wall (5000PSI @28 days) WITH 12mm rebar G60; fy420 (200mm bothways)

- 4. 4-400mmX400mm1200mm 34.48MPa Cast in place reinforced Concrete Column (5000PSI @28 days) WITH 8-16mm vertical rebar G60 and 10mm ties
- 5. Concrete Formwork and Accessories Rental

DIVISION 04 - MASONRY

ISABELO DELOS REYES BUILDING(IDR)

- 1. 100mm Composite Sandwich Type Structural Panel (50mm expanded polystyrene core on high tensile wires, incl.Accessories :Flat mesh, Angle mesh and U-mesh) include 25mm concrete render on both sides paper finish

DIVISION 05 - METALS

ISABELO DELOS REYES BUILDING(IDR)

- 1. W10X68x 12m Wide Flange Structural Metal Framing [include 1 coat epoxy primer+2 coats epoxy top coat,spray applied]
- 2. W10X68x 10m Wide Flange Structural Metal Framing [include 1 coat epoxy primer+2 coats epoxy top coat,spray applied]
- 3. W10X45x 6m Wide Flange Structural Metal Framing [include 1 coat epoxy primer+2 coats epoxy top coat,spray applied]
- 4. W8X30x 6m Wide Flange Structural Metal Framing [include 1 coat epoxy primer+2 coats epoxy top coat,spray applied]
- 5. MS Plate 4'x8'x 12mm [include 1 coat epoxy primer+2 coats epoxy top coat,spray applied]
- 6. Stair Metal pan Riser Gauge 14 (317x1300mm)
- 7. Stair Metal pan Tread Gauge 14 (275x1300mm)
- 8. Landing Metal pan Gauge 14 (2600x1200mm)
- 9. MS Plate 4'x8'x20mm [include 1 coat epoxy primer+2 coats epoxy top coat,spray applied]
- 10. ASTM A325 20mmØ x 500mm L-Anchor Bolt[include A325 High Tensile Nut and Washer]
- 11. All electric arc welding and cutting accessories, and consumables for welding work with zinc epoxy primer 3 coats + Weld Electrode E7018 3/16" x 14"; (fy: 415-570 MPa); Welding Works [Entrance Lobby Building]

DIVISION 07 - THERMAL & MOISTURE PROTECTION

ISABELO DELOS REYES BUILDING(IDR)

Dampproofing and Waterproofing

- 1. 4 coats Liquid Applied Roof Waterproofing with Fleece Reinforcement Mesh (Sikalastic 560 with Fleece or equivalent, quantity includes edge seams and overlaps)

DIVISION 08 - DOORS & WINDOWS

ISABELO DELOS REYES(IDR) BUILDING

- 1. Curtain Wall Assembly- 6mm Clear Tempered Float Glass panels on 102mm x 44mm x 1mm spaced @ 800mm Aluminum Powder Coated black finish Mullion with Awning Aluminum Windows

DIVISION 9- FINISHES

ISABELO DELOS REYES(IDR) BUILDING

Tiling

- 1. 3mm Non-Slip Self Leveling Epoxy Floor Topping (Polygard SLT 3021, Nippon9100F|911SL1 or approved equivalent)

- 2. 600mmx600mmx10mm Non-Slip Homogeneous Floor Tile Stain Resistant High Quality (Huanqui BXT2701E Iskar Coffee or equivalent) (include grout and Tile Adhesive + Silicone Expansion Joints)

Paints and Coatings

- 1. Semi-Gloss Acrytex Paint Finish (includes Preparation, 1 Coat Flat Primer, 2 Coats Finish Class AAA Finish) on prepared Expanded Polystyrene(EPS) Panels

ADDED ITEMS FROM THE BID FORM

DIVISION 26 - ELECTRICAL

UPB NEW CAC BUILDING

- 1. SERVICE ENTRANCE FROM MAIN POWER SUBSTATION TO NEW CAC BUILDING.
THHN Electrical wire 100 mm² - 200 lm
TW Electrical wire 50 mm² - 100 lm
65mmØ HDPE Spiral Flexible Conduit for electrical - 100 lm
Conduit Fittings and Accessories - 1 lot

CHANGED QUANTITIES FROM THE BID FORM

DIVISION 05 - METALS

UPB ENTRY

- 2. 19mm Eye and Eye Turnbuckle Drop Forged Carbon Steel, Galvanized and Meets design requirements of ASTM F1145, Type 1, Grade 1, Class D - **Change material quantity from 50 to 54 pcs.**

HKP-KA BOARDWALK

- 1. ½"Ø Plain Round Bar @ 6m for Cross Bracing [include Hot-Dip Galvanization] - **Change material quantity from 106 to 112 pcs.**
- 2. 19mm Eye and Eye Turnbuckle Drop Forged Carbon Steel, Meets design requirements of ASTM F1145, Type 1, Grade 1, Class D - **Reduce material quantity from 430 to 215 pcs.**

For guidance and information of all concerned.

(Sgd.)JESSICA K. CARIÑO
BAC Chairman

Received by the Bidder: _____
Date : _____