

PROJECT: **SUPPLY OF LABOR AND MATERIALS FOR THE REPAIR/ REHABILITATION OF EXISTING SUMP TANK AND INSTALLATION OF FLOOR DRAIN AT THE EXISTING PUMP HOUSE**

LOCATION: UP- BAGUIO

SUBJECT: BILL OF QUANTITIES

DURATION: 15 CD

I. MATERIALS

Qty	Unit	Description	Unit cost	Amount	
2	pcs.	4' x 8' welded wire mesh (3.5mm Ø)		Php	
15	bags	Portland cement		Php	
2	cu.m.	Washed sand		Php	
2	cu.m.	1/2" gravel		Php	
70	pcs.	4" CHB		Php	
5	pcs.	10mmØ x6m RSB		Php	
1	kg.	#16 tie wire		Php	
1	pc.	0.15m x 0.20m x 4.5mm thk. Metal plate		Php	
0.5	kg.	Welding rod		Php	
1	gal	Rust converter		Php	
2	gal	Metal epoxy primer		Php	
2	gal	Quick-drying enamel		Php	
1	lit.	Paint thinner		Php	
2	pc.	4" Paint brush		Php	
2	pcs.	Steel brush		Php	
2	pcs.	3"Ø PVC pipe		Php	
1	pc.	3"Ø PVC elbow		Php	
1	pc.	4" x 4" floor drain		Php	
1	can	Solvent cement (400 cc)		Php	
Total Php					-

II. LABOR COST

No.	Duration	Manpower	Rate		Amount
2	13	Skilled Laborers		Php	-
1	13	Laborer		Php	-
Total Php					-

III. EQUIPMENT RENTALS

Qty	Unit	Description	Rate	Duration	Amount
1	unit	Welding Machine		1	Php
1	unit	Jackhammer		1	Php
1	set	Electric Grinder		1	Php
Total				PHp	

TOTAL DIRECT COST Php

CONTRACTOR'S PROFIT Php

5% VAT Php

TOTAL PROJECT COST Php

- SCOPE OF WORK:
1. Construction of containment wall at the perimeter
2. Repair of leaking portion of the tank.
3. Concrete topping of the tank top.
4. Repainting works.
5. Installation of floor drain of the existing pump house.

Printed name/signature

Tel.no./cellphone no./e-mail address

Date

