

PROJECT: Labor and Materials for the Repair of SRC Canopy
LOCATION: College of Science
 University of the Philippines Baguio Campus, Governor Pack Road, Baguio City, PH
SUBJECT: Bill of Quantities
DURATION: 60 calendar days

ITEM NO.	DESCRIPTION	QTY	UNIT	MATERIAL UNIT COST	TOTAL MATERIAL COST	LABOR UNIT COST	TOTAL DIRECT COST	OCM	VAT 5%	SUBTOTAL	TOTAL
1 GENERAL REQUIREMENTS											
	Mobilization and Demobilization	1.00	lot								
	Construction facilities Cost (Field Office, First Aid Facilities, Sanitary Facilities)	1.00	lot								
	Equipment and Tools	1.00	lot								
	Scaffolding Rental	1.00	lot								
	Safety Provision (See Project Manual for Details)	1.00	lot								
	Cleaning and Waste Management Cost (Progress Cleaning, Site Maintenance, Construction Waste management and Disposal, Final Cleaning)	1.00	lot								
	DIVISION 1 SUBTOTAL										
2 WATERPROOFING AND DAMPROOFING											
	0.6mm x 0.610m Pre-painted Aluminum Zinc Alloy Coated Steel Charcoal Grey (Metalink Ecolock or equivalent) -include Corner, Upper, Lower, and End Moulding, Blind Rivets and TekscREW	40.00	sqm								
	0.6mm x 0.610m Pre-painted Aluminum Zinc Alloy Coated Steel Charcoal Grey (Metalink Ecolock or equivalent) -include Corner, Upper, Lower, and End Moulding, Blind Rivets and TekscREW	144.00	sqm								
	500mm Gutter from Bended 0.6mm PlainSheet (include Flashings, Blind Rivet Mounts and TekscREW attachments)	4.70	lm								
	DIVISION 2 SUBTOTAL										
3 FINISHES											
	Semi-Gloss Latex Paint Finish (includes Preparation, 1 Coat Flat Primer, 2 Coats Finish Class AAA Finish) on prepared Plasterboard Walls	1.00	sqm								
	DIVISION 3 SUBTOTAL										
	TOTAL										

Prepared by:

SIGNATURE OVER PRINTED NAME OF BIDDER

DATE