

PROJECT: Labor and Materials for the Repair of SRC Canopy
 LOCATION: College of Science
 University of the Philippines Baguio Campus, Governor Pack Road, Baguio City, PH
 SUBJECT: Bill of Quantities
 DURATION: 60 calendar days

| ITEM NO. | DESCRIPTION | QTY (A) | UNIT | MATERIAL UNIT COST (B) | TOTAL MATERIAL COST (C) = (A x B) | LABOR UNIT COST (D) | TOTAL LABOR COST (E) = (A x D) | TOTAL DIRECT COST (F) = (C + E) | OCM (G) = (F x 0.25) | VAT 5% (H) = (F + G) x 0.05 | TOTAL INDIRECT COST (I) = (G + H) | TOTAL (J) = (F + I) |
|----------|--|--------------|------|-----------------------------|--|--------------------------|---------------------------------------|--|-----------------------------|------------------------------------|--|----------------------------|
| 1 | GENERAL REQUIREMENTS | | | | | | | | | | | |
| | Mobilization and Demobilization | 1.00 | lot | N/A | | | | | | | | |
| | Construction Facilities Cost (Field Office, First Aid Facilities, Sanitary Facilities) | 1.00 | lot | N/A | | | | | | | | |
| | Equipment and Tools | 1.00 | lot | N/A | | | | | | | | |
| | Scaffolding Rental | 1.00 | lot | N/A | | | | | | | | |
| | Safety Provision (See Project Manual for Details) | 1.00 | lot | N/A | | | | | | | | |
| | Cleaning and Waste Management Cost (Progress Cleaning, Site Maintenance, Construction Waste management and Disposal, Final Cleaning) | 1.00 | lot | N/A | | | | | | | | |
| | DIVISION 1 SUBTOTAL | | | | | | | | | | | |
| 2 | WATERPROOFING AND DAMPROOFING | | | | | | | | | | | |
| | 0.6mm x 0.610m Pre-painted Aluminum Zinc Alloy Coated Steel Charcoal Grey[Metalink Ecolock or equivalent]- Include Corner, Upper, Lower and End Moulding, Blind Revits and Tekscrow [includes preparation of existing steel structure for roof attachment: cleaning of rusted surface, 3 coats of red oxide primer] and replacement of damaged 4.5mm fibercement board[Semi-Gloss Latex Paint Finish; includes Preparation, 1 Coat Flat Primer, 2 Coats Finish Class AAA Finish] | 40.00 | sqm | | | | | | | | | |
| | 0.6mm x 0.610m Pre-painted Aluminum Zinc Alloy Coated Steel Charcoal Grey[Metalink Ecolock or equivalent]- Include Corner, Upper, Lower and End Moulding, Blind Revits and Tekscrow; preparation of existing steel structure for roof attachment: cleaning of rusted surface, 3 coats of red oxide primer] | 144.00 | sqm | | | | | | | | | |
| | 500mm Gutter from Banded 0.6mm PlainSheet[include flashings, blind revit mounts and tekscrow attachments] | 4.70 | lm | | | | | | | | | |
| | DIVISION 2 SUBTOTAL | | | | | | | | | | | |
| 3 | FINISHES | | | | | | | | | | | |
| | Semi-Gloss Latex Paint Finish (includes Preparation, 1 Coat Flat Primer, 2 Coats Finish Class AAA Finish) on prepared Plasterboard Walls | 1.00 | sqm | | | | | | | | | |
| | DIVISION 3 SUBTOTAL | | | | | | | | | | | |
| | TOTAL | | | | | | | | | | | |

Prepared by:

SIGNATURE OVER PRINTED NAME OF BIDDER

DATE