

PROJECT: Labor and Materials for the Repair of SRC Canopy
 LOCATION: College of Science
 University of the Philippines Baguio Campus, Governor Pack Road, Baguio City, PH
 SUBJECT: Bill of Quantities
 DURATION: 60 calendar days

ITEM NO.	DESCRIPTION	QTY (A)	UNIT	MATERIAL UNIT COST (B)	TOTAL MATERIAL COST (C) = (A x B)	LABOR UNIT COST (D)	TOTAL LABOR COST (E) = (A x D)	TOTAL DIRECT COST (F) = (C + E)	OCM(15%) + Profit (10%) (G)	VAT 5% (H) = (F+G) x 0.05	TOTAL INDIRECT COST (I) = (G + H)	TOTAL (J) = (F + I)
1	GENERAL REQUIREMENTS											
	Mobilization and Demobilization	1.00	lot	N/A								
	Construction facilities Cost (Field Office, First Aid Facilities, Sanitary Facilities)	1.00	lot	N/A								
	Equipment and Tools	1.00	lot	N/A								
	Scaffolding Rental	1.00	lot	N/A								
	Safety Provision (See Project Manual for Details)	1.00	lot	N/A								
	Cleaning and Waste Management Cost (Progress Cleaning, Site Maintenance, Construction Waste management and Disposal, Final Cleaning)	1.00	lot	N/A								
	DIVISION 1 SUBTOTAL											
2	WATERPROOFING AND DAMPROOFING											
	0.6mm x 0.610m Pre-painted Aluminum Zinc Alloy Coated Steel Charcoal Grey[Metalink Ecolock or equivalent]- Include Corner, Upper, Lower and End Moulding, Blind Revits and Tekscrow [includes preparation of existing steel structure for roof attachment: cleaning of rusted surface,3 coats of red oxide primer] and replacement of damaged 4.5mm fibercement board[Semi-Gloss Latex Paint Finish; includes Preparation, 1 Coat Flat Primer, 2 Coats Finish Class AAA Finish]	40.00	sqm									
	0.6mm x 0.610m Pre-painted Aluminum Zinc Alloy Coated Steel Charcoal Grey[Metalink Ecolock or equivalent]- Include Corner, Upper, Lower and End Moulding, Blind Revits and Tekscrow; preparation of existing steel structure for roof attachment: cleaning of rusted surface,3 coats of red oxide primer]	144.00	sqm									
	500mm Gutter from Bended 0.6mm Plain sheet[include flashings, blind revit mounts and tekscrow attachments]	4.70	lm									
	DIVISION 2 SUBTOTAL											
3	FINISHES											
	Semi-Gloss Latex Paint Finish (includes Preparation, 1 Coat Flat Primer, 2 Coats Finish Class AAA Finish) on prepared Plasterboard Walls	1.00	sqm									
	DIVISION 3 SUBTOTAL											
	TOTAL											

Prepared by:

SIGNATURE OVER PRINTED NAME OF BIDDER

DATE