

**PROJECT:** Labor and Materials for the Dry Wall and Enclosure Removal for the Cultural Hub  
**LOCATION:** UPB Cultural Hub  
 University of the Philippines Baguio Campus, Governor Pack Road, Baguio City, PH  
**SUBJECT:** Bill of Quantities  
**DURATION:** 09 calendar days

ITEM NO.	DESCRIPTION	QTY	UNIT	ESTIMATED DIRECT COST	MARK-UPS IN PERCENT		TOTAL MARK-UP VALUE		5% VAT  (10) = 5%x[(5)+(9)]	TOTAL INDIRECT COST  (11)=(9)+(10)	TOTAL COST  (12)=(5)+(11)	UNIT COST  (13)=(12)/(3)
					OCM  (6)	PROFIT  (7)	%  (8)=(6)+(7)	VALUE  (9)=(5)x(8)				
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)=(6)+(7)	(9)=(5)x(8)	(10) = 5%x[(5)+(9)]	(11)=(9)+(10)	(12)=(5)+(11)	(13)=(12)/(3)
<b>1</b>	<b>GENERAL REQUIREMENTS</b>											
	Mobilization and Demobilization	1.00	lot		NA	NA	NA	NA				
	Removal of Exterior Dry Wall and Scaffolding at Front	1.00	lot		(15% max)	(10% max)	(25% max)					
	Safety Net for enclosing Site	200.00	l.m.		(15% max)	(10% max)	(25% max)					
	Safety Provision	1.00	lot		NA	(10% max)	(10% max)					
	<b>TOTAL</b>											

**SCOPE OF WORK:**

1. Remove by cutting the damaged metal studs from the undamaged installed metal studs
2. Remove the damaged metal studs from the ficem boards
3. Haul out and arrange all removed materials at level 3 of building
4. Remove scaffolding at the damaged portion of dry wall at front
5. Check and secure the connections of scaffoldings which are still held in place
6. Haul out and arrange all removed scaffoldings at level 3 of building
7. Install safety net as perimeter fence of the building

**Prepared by:**

\_\_\_\_\_  
 SIGNATURE OVER PRINTED NAME OF BIDDER

\_\_\_\_\_  
 DATE