

PROJECT: Labor and Materials for the Repair of SRC Canopy
LOCATION: College of Science
 University of the Philippines Baguio Campus, Governor Pack Road, Baguio City, PH
SUBJECT: Bill of Quantities
DURATION: 60 calendar days

ITEM NO.	DESCRIPTION	QTY (A)	UNIT	MATERIAL UNIT COST (B)	TOTAL MATERIAL COST (C) = (A x B)	LABOR UNIT COST (D)	TOTAL LABOR COST (E) = (A x D)	TOTAL DIRECT COST (F) = (C + E)	OCM (15%) + Profit (10%) (G)	VAT 5% (H) = (F+G) x 0.05	TOTAL INDIRECT COST (I) = (G + H)	TOTAL (J) = (F + I)
1 GENERAL REQUIREMENTS												
	Mobilization and Demobilization	1.00	lot	N/A	N/A							
	Construction facilities Cost (Field Office, First Aid Facilities, Sanitary Facilities)	1.00	lot	N/A	N/A							
	Equipment and Tools											
	Scaffolding Rental	1.00	lot	N/A	N/A							
	Safety Provision (See Project Manual for Details)	1.00	lot	N/A	N/A							
	Cleaning and Waste Management Cost (Progress Cleaning, Site Maintenance, Construction Waste management and Disposal, Final Cleaning)	1.00	lot	N/A	N/A							
	DIVISION 1 SUBTOTAL				N/A							
2 WATERPROOFING AND DAMPROOFING												
	0.6mm x 0.610m Pre-painted Aluminum Zinc Alloy Coated Steel Charcoal Grey [Metalink Ecoblock or equivalent] - Include Corner, Upper, Lower and End Moulding, Blind Revits and Tekscrow [includes preparation of existing steel structure for roof attachment: cleaning of rusted surface, 3 coats of red oxide primer] and replacement of damaged 4.5mm fiberement board [Semi-Gloss Latex Paint Finish; includes Preparation, 1 Coat Flat Primer, 2 Coats Finish Class AAA Finish]	40.00	sqm									
	0.6mm x 0.610m Pre-painted Aluminum Zinc Alloy Coated Steel Charcoal Grey [Metalink Ecoblock or equivalent] - Include Corner, Upper, Lower and End Moulding, Blind Revits and Tekscrow: preparation of existing steel structure for roof attachment: cleaning of rusted surface, 3 coats of red oxide primer]	144.00	sqm									
	500mm Gutter from Banded 0.6mm Plain sheet [include flashings, blind revit mounts and tekscrow attachments]	4.70	lm									
	DIVISION 2 SUBTOTAL											
3 FINISHES												
	Semi-Gloss Latex Paint Finish (includes Preparation, 1 Coat Flat Primer, 2 Coats Finish Class AAA Finish) on prepared Plasterboard Walls	1.00	sqm									
	DIVISION 3 SUBTOTAL											
	TOTAL											

Prepared by:

SIGNATURE OVER PRINTED NAME OF BIDDER

DATE