

PROJECT: FLOOR FINISHING, INSTALLATION OF PARTITION WALL WITH DOOR, PROVISION OF WINDOW, AND INSTALLATION OF ENTRANCE DOOR AT LEVEL 5 HKP BUILDING
LOCATION: College of Science
University of the Philippines Baguio Campus, Governor Pack Road, Baguio City, PH
SUBJECT: Bill of Quantities
DURATION: 30 calendar days (Includes Lead Time for Glass Tempering)

ITEM NO.	DESCRIPTION	QTY	UNIT	MATERIAL UNIT COST	LABOR & EQUIPMENT UNIT COST	MATERIAL COST	LABOR COST	TOTAL DIRECT COST	OVERHEAD, CONTINGENCY AND MISCELLANEOUS EXPENSES OCM (15%)	CONTRACTOR'S PROFIT (10%)	VAT (5%)	TOTAL INDIRECT COST	TOTAL COST
1	GENERAL REQUIREMENTS												
	Mobization/ Demobalization	1.00	lot	NA		NA			NA	NA			
	Safety provision												
	Part-time Safety Officer	5.00	day	NA		NA			NA				
	First Aid Kit	1.00	lot		NA		NA		NA				
	Miscellaneous	1.00	lot		NA		NA		NA				
	Personal Protective Equipment(PPE)												
	a. Safely Helmet	56.00	man-days		NA		NA		NA				
	b. Safety Shoes	56.00	man-days		NA		NA		NA				
	c. Safety Gloves	56.00	man-days		NA		NA		NA				
	Signages and Barricades												
	a. PPE Signage (4' x 8')	1.00	set		NA		NA		NA				
	b. Safety First (4' x 4')	1.00	set		NA		NA		NA				
	c. Warning Signs (2' x 3')	8.00	set		NA		NA		NA				
	d. Caution Tape, 100ft.	1.00	roll		NA		NA		NA				
2	FLOOR FINISHES												
	Surface Preparation												
	Steel wire cup brush for grinder	10.00	pc										
	Sand paper	6.00	yard										
	Stopa rugs	40.00	pc										
	Paints and Coatings												
	Epoxy Primer white, with curing agent	16.00	gal										
	Epoxy Enamel top coat, with curing agent	25.00	gal										
	Epoxy Thinning Solvent	10.00	gal										
	Miscellaneous	1.00	lot										
3	GLASS PARTITIONS AND WALLS												
	Partition Wal with Door, Glass Door, and Curtain wall												
	1.2 x2.2m Curtain Wal Assembly- 6m Clear Tempered Float Glass panels on 102mm x 44mm x 1mm Aluminum Powder Coated white finish Mullion with Sliding Windows (See Drawings)	2.64	sq.m.										
	2.6m H x 26.m W Aluminum casement glass sliding door partition, (8mm thick ordinary glass)	1.00	set										
	1600 x 2100 Frameless Glass Double Door (12mm thick, tempered) whti universal patch fittings and lockset (Dorma or equivalent) with Stainless Door handles (Dorma MDZ 8210 or equivalent), with fixed 12mm tempered on sides	1.00	set										
	TOTAL												

Prepared by:

SIGNATURE OVER PRINTED

DATE